

NAME OF WORK :- Construction of Hall with Dome Roof at Arthuna [SIZE
20 M X 30 M]

GENERAL ABSTRACT OF COST

PART 'A' CIVIL WORK GROUND FLOOR	Rs.	3575752.32
----------------------------------	-----	------------

PART 'B' ELECTRIC WORK @ 12% OF Civil Work	Rs.	429090.28
--	-----	-----------

TOTAL Rs.	4004842.60
-----------	------------

Add @ 2 % for Electric Fixtures On Civil Work Part 'A'
i.e. on Rs.

3575752.32	Rs.	71516.00
------------	-----	----------

GRAND TOTAL Rs.	4076358.60
-----------------	------------

SAY Rs. **40.76**
Lacs.

**CHARTERED ENGINEER,
RKS TECHNO-LEGAL CONSULTANTS, UDAIPUR**

NAME OF WORK :- Construction of Hall with Dome Roof at Arthuna [SIZE 20 M X 30 M]

PART 'A' CIVIL WORK BASEMENT, GROUND FLOOR

ABSTRACT OF COST

S.No.	Particulars.	Quantity		Rate	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	720.00	Cum	178	P Cum	128160.00
2	Filling available excavated earth (excluding rock) in trenches, plinth side of foundation etc. in layers not exceeding 20 cm. in depth , consolidating each deposited layer by ramming and watering including lead upto 50Mtr. and lift upto 1.5Mtr.	526.40	Cum	64	P Cum	33689.60
3	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering =All up to plinth leve 1:4:8 (1Cement :4 Coarse Sand :8 Graded stone aggregate 40 mm nominal size	22.08	Cum	3302	P Cum	72908.16
4	Providing and laying in position specified grade of reinforcement cement concrete all RCC structural elements upto plinth level including curing compaction finishing with rendering in cement sand mortar 1:3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering shuttering and reinforcementlevel. M25 grade Design mix	34.80	Cum	5003	P Cum	174104.40
5	Centering and shuttering with plywood or steel sheets including strutting, propping, bracing both ways and removal of formwork for foundations in basements rafts, footings, strap beams, bases of columns , etc. up to plinth level.	69.48	Sqm	157	P Sqm	10908.36

S.No.	Particulars.	Quantity		Rate	Unit	Amount
6	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor three level. Tremo Mechanically treated bars	3588	Kg	77	P Kg	276276.00
7	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : : Cement mortar 1 : 6 (1 cement : 6 coarse sand)	59.74	Cum	4990	P Cum	298080.64
8	Random Rubble stone masonry for foundation and plinth in Cement Sand mortar above 30 CM thick wall in: Cement Mortar 1:6 (1-Cement : 6-Sand).	54.00	Cum	2838	P Cum	153252.00
9	Plaster on new surface on walls in cement sand mortar 1:6 including raking of joints etc. complete fine finished : 20 mm thick.	765.12	Sqm	190.00	P Sqm	145373.00
10	Providing and fixing T-iron/angle iron frames for doors windows and ventilators of mild steel tee or angle sections joints mitred and welded with 15 x 3 mm lugs, 10 cm. long embedded in cement concrete blocks 15x15x10 cm. size of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips and screws or with bolt and nuts as required including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.	138.12	Kg	83	P Kg	11463.98

S.No.	Particulars.	Quantity		Rate	Unit	Amount
11	Providing & fixing steel glazed doors, windows and ventilators shutters of standred rolled steel section joint mitred and welded with steel 13x3mm lugs 10 Cm. long embedded in cement concrete blocks 15x10x10 Cm. of 1:3:6 (1-Cement:3-coarse sand:6-graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of plain glass panes 4mm thick with copper glazing clips and special metal-sash putty of approved make, or metal beading with screws complete including priming coat of approved steel primer, excluding the cost of metal beading and other fittings except necessary hinges of pivots steel handles and peg stay etc. as required. Patially fixed and partially openable fixed area not exceed 33%	17.28	Sqm	3090	P Sqm	53395.20
12	Supplying and fixing fixed wire gauge of 14 mesh x 24 gauge to the metal frame of rolled section by metal beading 20x3mm with suitable screw at not exceeding 150 mm distance.	1.73	Sqm	617		1066.18
13	Providing and fixing Square bars or other flat welded to window, ventilators etc.	162.72	Kg	65		10576.80
14	Polished Blue Kota Stone flooring skirting, laid over 20 mm thick base of C.M. 1:4 and jointed with grey cement slurry to match the shade of the slab including rubbing and polishing complete : For area of each slab up to 2001 to 5000 Sq. Cm : (A) 25 mm thick slab.	600.00	Sqm	1023		613800.00
15	Random rubble dry stone Kharanja under floor.	137.75	Cum	932	P Cum	128383.00
16	White washing with lime to give an even shade including all scaffolding: New work (two or more coats).	330.12	Sqm	11.00	P Sqm	3632.00
17	Colour washing of all shades to give an even shade including all scaffolding: New work (two or more coats) with a base coat of white washing with lime.	435.00	Sqm	14.00	P Sqm	6090.00

S.No.	Particulars.	Quantity		Rate	Unit	Amount
18	Applying priming coat with ready mix pink or Grey primer of approved brand and manufacture on wood work hard and soft wood.	73.28	Sqm	29.00	P Sqm	2126.00
19	Painting with enamel paint of approved brand and manufacture to give an even shade two or more coats on new work.	73.28	Sqm	69.00	P Sqm	5057.00
20	Supply and installation of Multi Rib Proofing/cladding Sheet Manufacture out of 0.50mm TCT (Total Coated Thickness) high tensile Zinc aluminum alloy coated galvalume steel (as per 150gsm zinc aluminum coated 550Mpa tensile strength) confirming to IS: 1397/astm A-792 sheet to have wide ribs 30mm high NB at 250 centre and centre width of 1020mm sheets be coated with regular modified polyester system on a continuous with line on centre for face and with a polyester coating respectively sheet shall have proportionality with siphoned plate made to prevent leakage sheet shall be fixed by more of self drilling self tapping hot dip zinc coated hex head fastener of size 12x14x55mm long. The sheet shall be supplied in cost one length and for a minimum up to 12mts with all scaffolding.	600.00	Sqm	689.00	P Sqm	413400.00
21	Add extra for 0.60mm TCT (Total Coated Thickness) high tensile Zinc aluminum alloy coated galvalume steel sheet in place of 0.50mm thick	600.00	Sqm	103.35	P Sqm	62010.00
22	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting (height upto 10 m) , fixing in position and applying a priming coat of approved steel primer all complete:	#####	Kg	81.00	P Kg	972000.00
				Total	Rs.	3575752.32

**CHARTERED ENGINEER,
RKS TECHNO-LEGAL CONSULTANTS, UDAIPUR**

NAME OF WORK :- Construction of Hall with Dome Roof at Arthuna [SIZE 20 M X 30 M]

PART 'A' CIVIL WORK FIRST FLOOR
DETAILS OF MEASUREMENTS

S.N.	Particulars	Nos.	Length	Breadth	Height	Qty.	Units
	<u>Center to center distances</u>						
	<u>Ground Floor</u>						
	<u>Main walls 230 mm th. in X and Y Direction</u>						
		2	x	20.00	=	40.00	RM
		2	x	30.00	=	60.00	RM
					TOT,=	100.00	RM
	<u>PARAPET WALL 230 MM</u>						
	Back Side	1	x	0.00	=	0.00	RM
					TOT,=	0.00	RM
	<u>Brick Partition walls in X and Y Direction</u>						
		1	x	0.00	=	0.00	RM
					TOT,=	0.00	RM
1	Earth work in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift up to 1.5 Mtr. including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed within a lead of 50 meter. All kinds of soil.						
		1	x	20.00	x	30.00	x 1.20 = 720.00 Cum
				Total			720.00 Cum
2	Filling available excavated earth (excluding rock) in trenches, plinth side of foundation etc. in layers not exceeding 20 cm. in depth , consolidating each deposited layer by ramming and watering including lead upto 50Mtr. and lift upto 1.5Mtr. Average Width (49.83+18.44)/2=34.14 Area of Open Excavation					0	
		1	x	20.00	x	30.00	= 600.00 Sqm
	<u>Deductions</u>						
	Footing Area						
	C1	16	x	2.00	x	2.30	= 73.60 Sqm
				Total Deductions		-	73.60 Sqm
	Net earth Filling Area			600.00 - 73.60	=	526.40	Sqm
	Qty. in Filling			526.40	x	1.00	= 526.40 Cum
				Total			526.40 Cum

S.N.	Particulars	Nos.	Length	Breadth	Height	Qty.	Units
3	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering =All up to plinth level 1:4:8 (1Cement :4 Coarse Sand :8 Graded stone aggregate 40 mm nominal size <u>FOOTING</u> F1	16	x	2.00 x	2.30	x 0.30 =	22.08 Cum
						Total Qty.	22.08 Cum
4	Providing and laying in position specified grade of reinforcement cement concrete all RCC structural elements upto plinth level including curing compaction finishing with rendering in cement sand mortar 1:3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering shuttering and reinforcement level. M25 grade Design mix <u>FOOTING</u> F1	16	x	1.70 x	2.00	x 0.60 =	32.64 Cum
TOTAL QTY IN FOOTING COLUMNS		32.64	Cum				
	C1	16	x	0.30 x	0.60	x 0.75 =	2.16 Cum
						Total Qty.	34.80 Cum
5	Centering & shuttering with plywood or steel sheets including strutting propping, bracing both ways with wooden members and removal of form work for superstructure upto 4.5 Mtr. height above plinth level (A) For Columns, Pillars, Posts and Struts etc.						
	<u>Footing</u>	12	x	7.40 x	0.60	=	53.28 Sqm
	<u>Columns C1</u>	12	x	1.80 x	0.75	=	16.20 Sqm
						Total	69.48 Sqm
6	Providing and fabrication steel reinforcement for R.C.C. work including cutting, bending, placing in position and binding complete including cost of binding wire in foundations, Raft footing step Beams base of column etc. upto plinth level. Hot rolled deformed (IS : 1139) cold twisted (IS : 1786) bars.						
	Footings	32.64	Cum @	100 Kg/Cum	=	3264	Kg
	Columns	2.16	Cum @	150 Kg/Cum	=	324	Kg
						Total	3588 Kg

S.N.	Particulars	Nos.	Length	Breadth	Height	Qty.	Units
7	Brick work in superstructure upto 4.5 metre height above plinth level Cement Mortar 1:6 with bricks are class designation 75.						
	<u>Walls in X AND Y direction</u>	1	x 100.00	x 0.23	x 3.00	= 69.00	Cum
			Gross Qty.			+ 69.00	Cum
	<u>Deductions</u>						
	D1	4	x 1.50	x 0.23	x 2.10	= 2.90	Cum
	W1	8	x 1.80	x 0.23	x 1.20	= 3.97	Cum
	<u>Lintels</u>	1	x 100.00	x 0.23	x 0.23	= 5.29	Cum
			Total Deductions			- 9.26	Cum
	Net qty.		69.00	- 9.26	=	59.74	Cum
8	Random Rubble stone masonry for foundation and plinth in Cement Sand mortar above 30CM thick wall in: Cement Mortar 1:6 (1-Cement : 6-Sand).						
	<u>Walls in X AND Y direction</u>	1	x 100.00	x 0.60	x 0.90	= 54.00	Cum
			Total			54.00	Cum
9	Plaster on new surface on walls in cement sand mortar 1:6 including raking of joints etc. complete fine finished : 20 mm thick.						
	<u>GROUND FLOOR INSIDE PLASTER</u>						
	Main Walls	2	x 20.00	x 3.60	=	144.00	Sqm
	Main Walls	2	x 30.00	x 3.60	=	216.00	Sqm
			Gross Qty.			+ 360.00	Sqm
	<u>Deductions</u>						
	D1	4	x 1.50	x 2.10	=	12.60	Sqm
	W1	8	x 1.80	x 1.20	=	17.28	Sqm
			Total Deductions			- 29.88	Sqm
	Net qty. of Internal Plaster in GF		360.00	- 29.88	=	330.12	Sqm
	<u>External plaster</u>						
		2	x 20.00	x 4.35	=	174.00	Sqm
		2	x 30.00	x 4.35	=	261.00	Sqm
			Gross qty. of External Plaster (+)			= + 435.00	Sqm
	Net qty. of External Plaster in FF		435.00	- 0.00	=	435.00	Sqm
	Total qty. of Plaster		330.12	+ 435.00	=	765.12	Sqm

S.N.	Particulars	Nos.	Length	Breadth	Height	Qty.	Units
10	Providing and fixing T-iron/angle iron frames for doors windows and ventilators of mild steel tee or angle sections joints mitered and welded with 15 x 3 mm lugs, 10 cm. long embedded in cement concrete blocks 15x15x10 cm. size of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips and screws or with bolt and nuts as required including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.						
D1		4	x(1.80 +	2.15 +	2.15)=	33.28 RM	
				Total		33.28 RM	
			33.28 RM	@ 4.15 Kg/m		138.12 Kg	
11	Providing and fixing steel glazed doors windows and ventilator shutters of standard rolled steel section joints mitered and welded with steel lugs 13x3 mm, 10 cm long embedded in cement concrete block 15x10x10 cm. of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or with fixing clips and screws or with bolt and nuts as required including providing & fixing of plain glass panes 3 mm thick with glazing clips and special metals sash putty of approved make or metal beading with screws complete including priming coat of approved steel primer excluding cost of metal beading and other fixing except necessary hinges of pivots steel handles peg stay etc. as required (Partly Fixed Partly Openable)						
W1		8	x 1.80 x	1.20	=	17.28 Sqm	
				Total		17.28 Sqm	
12	Providing and fixing square bars or other flat welded to window, ventilators etc.						
W1		8	x 1.80 x	10 @ 1.	1.13 =	162.72 Kg	
				Total		162.72 Kg	
13	Supplying and fixing wire gauge of 14 mesh x 24 gauge to the metal frame of rolled section by metal beading 20 x 3 mm with suitable screw at not exceeding 150 mm distance.						

S.N.	Particulars	Nos.	Length	Breadth	Height	Qty.	Units
	Qty. 10% of total windows area	17.28	x	0.10		1.73	Sqm
14	Polished Blue Kota Stone flooring skirting, laid over 20 mm thick base of C.M. 1:4 and jointed with grey cement slurry to match the shade of the slab including rubbing and polishing complete : For area of each slab up to 2001 to 5000 Sq. Cm : (A) 25 mm thick slab.						
		1.00 x	20.00 x	30.00	=	600.00	Sqm
				Total		600.00	Sqm
15	Random rubble dry stone Kharanja under floor.						
		1	x	19.00 x 29.00	x 0.25 =	137.75	Cum
				Total Qty.		137.75	Cum
16	Providing and fixing fully panelled double leaf shutter for doors as per approved design and drawings with approved ordinary C.P./oxidised steel fittings as per Annexure 'A' and width of styles & top rails of 100 mm and bottom & lock rails width of 150 mm and intermediate styles including teak wood mouldings and beading to 25x5 mm size on both face complete . Assam teak wood grade I 35 mm thick . 12 mm thick shuttering ply (Kit ply make) both faces panels.						
	D1	4	x	1.50 x	2.10	=	12.60 Sqm
				Total		12.60	Sqm
17	White washing with lime to give an even shade including all scaffolding: New work (two or more coats). Qty. of Internal Plaster						
					=	330.12	Sqm
				Total		330.12	Sqm
18	Colour washing of all shades to give an even shade including all scaffolding: New work (two or more coats) with a base coat of white washing with lime. Qty. of External Plaster						
		1 x	435.00		=	435.00	Sqm
				Total		435.00	Sqm
19	Applying priming coat with ready mix pink or Grey primer of approved brand and manufacture on wood work hard and soft wood. Double Leaf door shutters	12.60	Sqm	@	2.25 =	28.35	Sqm

S.N.	Particulars	Nos.	Length	Breadth	Height	Qty.	Units
	Windows	17.28		Sqm	@	2.60 =	44.93 Sqm
						Total =	73.28 Sqm

- 20 Painting with enamel paint of approved brand and manufacture to give an even shade two or more coats on new work.

Qty. of priming

73.28 Sqm

- 21 Supply and installation of Multi Rib Proofing/cladding Sheet Manufacture out of 0.50mm TCT (Total Coated Thickness) high tensile Zinc aluminum alloy coated galvalume steel (as per 150gsm zinc aluminum coated 550Mpa tensile strength) confirming to IS: 1397/astm A-792 sheet to have wide ribs 30mm high NB at 250 centre and centre width of 1020mm sheets be casted with regular modified polyster system on a continuous with line on centre for face and with a polyster coating respectively sheet shall have proportionality with siphoned plate made to prevent leakage sheet shall be fixed by more of self drilling lift tapping hot dip zinc coated hex head fastener of size 12x14x55mm long. The sheet shall be supplied in cost one length and for a minimum up to 12mts with all

Hall

1 x 20.00 x 30.00 = 600.00 Sqm
Total 600.00 Sqm

- 23 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting (height upto 10 m) , fixing in position and applying a priming coat of approved steel primer all complete:

Hall @ 20 kg per Sq M

1 x 20.00 x 600.00 = ##### Kg

**CHARTERED ENGINEER,
RKS TECHNO-LEGAL CONSULTANTS, UDAIPUR**